Name of Work : Improvements to road & drain at 18th Main Depot Muniswamappa Layout K.G halli and surrounding area in Ward No.12 Shettyhalli, Shettyhalli Sub Division.

Estimated cost : Rs 50 .00 lakhs  Job No : 012-18-000007

Head of a/c :Special Grant  P- 3332

## ROYALTY STATEMENT

| Sl No | Description of Item | Unit | Total Qty | Stone/Jelly | | Sand | | Remarks |
|---|---|---|---|---|---|---|---|---|
| | | | | constant | Qty | constant | Qty | |
| 1 | Providing and laying in position plain cement concrete of mix 1:4:8 | cum | 113.00 | 0.85 | 96.05 | 0.57 | 64.41 | |
| 2 | Reinforced cement concrete of design mix M20 | cum | 234.00 | 0.65 | 152.10 | 0.46 | 107.64 | |
| | Total | | | | 248.15 | | 172.05 | |

| Sl No | Material | Unit | Qty | Rate | Amount |
|---|---|---|---|---|---|
| 1 | Jelly/Metal | cum | 248.15 | 108.00 | 26800.00 |
| 2 | Sand | cum | 172.05 | 103.00 | 17721.00 |
| | Total amount | | | | 44521.00 |

Assistant Engineer
Ward No 12

Assistant Executive Engineer
Shettyhalli sub division, BBMP